FULTON TECHNOLOGIES
160 N. GARDEN AVE.
ROSELLE, IL 60172
(630) 893-1395

January 20, 2015

Chief of Police Russell C. Stokes
Town of Cortland Police Department
300 West Lincoln Highway
PO Box 519
Cortland, IL 60112-0519

RE: 2015 Annual Siren Maintenance Contract

Dear Chief Stokes:

Enclosed is your contract proposal to perform maintenance for the Town of Cortland Outdoor Warning Siren System on an annual basis for the period of January 1, 2015 through December 31, 2015. During this period we will visit each one of your sirens to perform the general maintenance, which is outlined for you in the maintenance contract. As you know, it is important to maintain your sirens to ensure they continue to perform during those times of severe weather when they are needed most. Any minor repairs needed on a siren will be performed immediately while on site to keep your costs down, however additional repair charges will apply. Major repairs found will require preapproval and you would be contacted before any major repairs were performed. Please call me with any questions you may have.

After acceptance, please sign and return the enclosed contract within 45 days. For your convenience, you may return the signed contract via mail, facsimile to 866-553-0053, or scan and email to sirens@fultontech.net. Thank you for your prompt attention and continued support.

Sincerely,
FULTON TECHNOLOGIES, INC

John E. Vistine

John E. Vistine
Technical Services

FULTON TECHNOLOGIES
160 N. GARDEN AVE.
ROSELLE, IL 60172
(630) 893-1395

Town of Cortland
2015 Outdoor Warning Siren System Annual Maintenance Contract

This is a contract proposal to perform annual maintenance for your Outdoor Warning Siren System. This includes the following on an annual basis for the calendar year of January 1, 2015 through December 31, 2015. We will perform the following:

- Clean and check contactors in control cabinets.
- Verify no moisture problems in control cabinets.
- Test Radio frequency, sensitivity, and audio levels.
- Check and verify decode signals on radio system.
- Test each command signal for proper timing and function.
- Check and test siren batteries and fill with distilled water if necessary. ***Change batteries if over five years old or fails load test.***
- Check and test siren charging system and all motor controls.
- Check antenna, antenna cable and connectors.
- Check and test grounding system and provide ground rod reading:
- Test siren head heater circuit and thermostat.
- Inspect all relay contacts and connections.
- Check for any apparent breakage, wear and tear or vandalism and report same to owner.
- Inspect siren equipment for looseness or any condition that may compromise the reliability and useful life of the equipment.
- Perform inspection of surge protections system and notify the owner of deficiencies.
- Growl test performed after completion of preventive maintenance.

This contract includes all labor, equipment and material for general maintenance. ***Any defective parts or components found will be repaired or replaced at an additional charge to the owner with an additional labor charge to perform the repair.*** This is in addition to the basic contract amount approved. If major repairs are necessary, we will contact the owner for approval.

Maintenance Amount: $1,043.16
Two (2) T-128s & One (1) Federal 2001

PLEASE! Do not send payment now, this is not a bill. You will be invoiced after maintenance is completed.

PROPOSED BY:

John E. Vistine
(Sign)

JOHN E. VISTINE

FULTON TECHNOLOGIES

Date: 1/20/2015

ACCEPTED BY:

(Sign)

RUSSELL C. STORES
(Print name)

MAYOR
(Title)

Date: 2-5-15