Swedberg Electric, INC
PO Box 376
Sycamore, IL 60178
Phone:815.895.8300 Fax:815.895.8313

September 21, 2016

Town of Cortland
Water/Wastewater Division
Attn: Joel Summerhill
Director of Water/Wastewater

Re: Blower Power

Proposal for Electrical Work

Swedberg Electric, Inc. is pleased to submit for your review the following proposal including material and labor necessary unless noted otherwise to complete the electrical work for the above referenced Blower Power based on the information provided.

Our Bid Includes:

- *Demo the existing 2" PVC conduit and wire that feeds the blower that will be removed.*
- *Remove the existing combination motor starter disconnect that feeds the blower that will be removed.*
- *Install a 75HP VFD supplied by others in the same location as the combination motor starter disconnect.*
- *Secure the control panel rack next to the new Inovair blower.*
- *Provide 120V power to the control panel from the nearest available circuit in the room.*
- *Furnish and install EMT conduit with 480V power from the VFD to the 75HP motor.*
- *Furnish and install flexible conduit to the motor for the 480V feed.*
- *Furnish and install conduit from the control panel to the VFD for controls.*
- *Install the nineteen pin cable supplied by others from the control panel to the blower.*
- *Furnish and install a flexible conduit from the control cabinet to the blower for the 120V.*

Our Bid Excludes:

- *Permits/Utility fees.*
- *Overtime.*
- *Ethernet cable.*

Our Bid shall be …… $6,876.00
Six thousand eight hundred seventy six and No/100 dollars

If you have any questions please feel free to call
Thank you for the opportunity to bid this project,

_____ _____

Approved By

Dan Hager
Project Manager / Estimator